

Grill Work & Painting for the Collapsible Gate in the New Administrative Building

Sl. No.	Items of Works	Qty	Unit	Rate in Figure	Rate in Words	Amount
1	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2 mm and braced with flat iron diagonals 20x5 mm size, with top and bottom rail of T-iron 40x40x6 mm, with 40 mm dia steel pulleys, complete with bolts, nuts, locking arrangement, stoppers, handles, including applying a priming coat of approved steel primer.	29.09	sqm			
2	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :					
	Two or more coats on new work					
	Qty same as item No 10.3	58.18	sqm			
	Total=	81.7	sqm			
3	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete.					
	Fixed to openings /wooden frames with rawl plugs screws etc.	141.1	kg			
<b>Grand Total</b>						
Say						

Rupees .....Only

Sealed Signature of the Tenderer  
Date

*Amel*

*AV*

*AV*