

## BOQ FOR REPAIRING OF DSW OFFICE

SI No	Description	Qty	Unit	Rate in Figure	Rate in Words	Amount (in Rs)
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.					
	Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)					
	Total=	0.81	cum			
2	12 mm cement plaster of mix : 1:4 (1 cement: 4 coarse sand)					
	Total=	18 00	sqm			
3	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete					
	Total=	360.10	sqm			
4	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete					
	Total=	360.10	sqm			
5	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound ) content. With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre					
	Total=	360.10	sqm			
6	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of Special primer applied @ 0.75 ltr /10 sqm					
	Total=	360.10	sqm			
7	Providing and laying cement concrete in kerbs, steps and the like at or near ground level excluding the cost of centering, shuttering and finishing. 1:1½:3 (1 Cement: 1½ coarse sand(zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)					

**BOQ FOR REPAIRING OF DSW OFFICE**

Sl No	Description	Qty	Unit	Rate in Figure	Rate in Words	Amount (in Rs)
		Total= 2.03	cum			
8	Neat cement punning					
		Total= 27.00	sqm			
9	Providing and fixing double glazed hermetically sealed glazing in aluminium windows, ventilators and partition etc. with 6 mm thick clear float glass both side, having 12 mm air gap, including providing EPDM gasket, perforated aluminium spacers, desiccants, sealant (Both primary and secondary sealant) etc. as per specifications, drawings and direction of Engineer-in-charge complete.					
	<b>Total</b>	<b>35.34</b>	sqm			
				Civil Works=		

Rupees ..... Only

Sealed Signature of the Tenderer


