

PRICE BID						
SI No	Description of Work	Unit	Qty	Rate	Rate in Words (Rs)	Amount (Rs)
DSR-2021 Item - 21.1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : 21.1.1 For fixed portion 21.1.1.2 Powder coated aluminium (minimum thickness of powder coating 50 micron)- Aluminium section external member 1.653 kg/m and internal member 1.692 kg/m	kg	630.00			
DSR-2021 Item -21.1.2	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately)21.1.2.2 Powder coated aluminium (minimum thickness of powder coating 50 micron). Al sections of 2.53kg /m.	kg	295.00			
DSR-2021 Item -21.2	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineerincharge. 21.2.2 Pre-laminated particle board with decorative lamination on both sides	sqm	110			
DSR-2021 Item-21.3	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item):21.3.1 With float glass panes of 4.0 mm thickness (weight not less than 10kg/sqm)	sqm	110			
DSR-2021 Item -2.31	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	sqm	500			
DSR-2021 Item-2.6	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-incharge 2.6.1 - All kinds of soil	cum	40			
DSR-2021 Item -18	Hire and running charges of loader	day	3			
NON DSR Item	Providing Manual pallet Mover with bearing capacity of 1000 kg	SUPPLY	1			
NON DSR Item	Providing One tripod lifting frame (2 ton capacity)	SUPPLY	1			
					Total Amount	
	Amount in Words (Rs)					

465

29